


HAZ SWITCH



HAZ Flash

3

1

2

W/G 3 - to fuse  12V RAW +
Key Switch #30

G 2 - HAZARD Indicator

Black 1 - to #6 on HAZARD Switch


TURN Flasher

1

2

Y-1 - to #2 on HAZARD Switch

A 2 - ~~12V~~ FUSE 12V + Light switch
W/B 2 singles



W/B Pin 3 T/S/switch 49A

B Pin 5 Right turn Lights

W/G Pin 7 Right turn Indicator

G Pin 4 Left turn Indicator

W/Y Pin 1 Left turn Lights

Y Pin 2 turn signal flasher

Black Pin 6 to #1 HAZARD flasher

TURN SIGNAL / HORN SWITCH

71 HORN BLACK


L Pin 4 ~~4~~ HAZ SWITCH w/indicator

49A Pin 3 HAZ SWITCH w/G

R Pin 7 HAZ SWITCH w/indicator


$2\frac{5}{8}$


$\frac{1}{2}$



Water Bus Rear Room w/ Bumper Room
5/10/82 (BT)


SIDE, PARK, LIC
BACK UP
BRAKE
GROUND
LEFT TURN
RIGHT TURN





1-11-58 RLY con

1 - 7-7-58 (11)
 2 - 1-12-58
 3 - 1-12-58
 4 - 1-12-58
 5 - 1-12-58
 6 - 1-12-58
 7 - 1-12-58
 8 - 1-12-58
 9 - 1-12-58
 (11) 9 Sp...
 (110)



WIRE HOOK UP

RED - 12V DC POS.

GRAY - 12V DC NEG (GND)

W/RED - RELAY COIL POS. 12V COIL

W/BLK - RELAY COIL NEG.

ORW - WARNING

2 BLK WIRES FROM TRANSFORMER

HOOK UP TO CHARGER INPUT (120VAC)

VIOLET WIRE
TO CONTROLLER

S. OHBA & ASSOCIATES CHICAGO, IL.	
SCALE: N/A	APPROVED BY:
DATE: 12-23-82	DRAWN BY: T.H.
CHARGER ON AND CONTROLLER INHIBIT	
DESIGNER: EV GARS	DRAWING NUMBER: B-6611374